

**AHMEDABAD MUNICIPAL CORPORATION**

**SOR - (Jan. -2016) for Central Verge / Footpath / Stone Paving**

Sr.	Item Description	Rate	Per	Rate Reference		
				SOR	I.Code	P.no.
1	Supplying and fixing of 380 mm H x 300 mm L x 200 mm B Kerb block <b>for Central Verge</b> in M-20 grade using 20 mm nominal size black trap aggregate of Sevaliya/Timba or equivalent quality for pre-cast blocks, reasonably exposed finish/ formwork, mould with well equipped with vibratory system for kerb stones of approved design including curing, etc. complete, including the cost of formwork etc. complete. The rate shall also include necessary cutting of asphalt, fixing the Kerb stones in line and level on 5 cm thick sand bedding with necessary equipments and materials. The rate shall also include the flush pointing in CM (1:3) for all joints of the kerbstones. Filling of zari along the sides of the kerb stone fixed with Bituminous concrete / C.C. mixed in proper position to flush with the road surface as directed by Engineer in charge to form a portable mixture. In any case Gravel or such type of materials shall not be allowed for production.	486.00	Rmt	ARC Rate		
2	Supplying and fixing of 300 mm-L x 150 mm-B x 380 mm-H Kerb block for Footpath in M-20 grade using 20 mm nominal size black trap aggregate of Sevaliya/Timba or equivalent quality for pre-cast blocks, reasonably exposed finish/ formwork , mould with well equipped with vibratory system for kerb stones of approved design including curing, etc. complete, including the cost of formwork etc. complete. The rate shall also include necessary cutting of asphalt, fixing the Kerb stones in line and level on 5 cm thick sand bedding with necessary equipments and materials. The rate shall also include the flush pointing in CM (1:3) for all joints of the kerbstones. Filling of zari along the sides of the kerb stone fixed with Bituminous concrete Bituminous concrete / C.C. mixed in proper position to flush with the road surface as directed by Engineer in charge to form a portable mixture.			ARC Rate		
	a) Laying on 5 cm thick Sand Bedding	393.00	RMT			
3	Providing and Laying of Rubber Moulded Paver Block Grey/Coloured 60 mm thick, M-35 Grade of any size ; shape (Usually Uni-Paver Blocks) using black trap good quality aggregate of 20 mm nominal size for footpath, parking areas, service lanes and other areas as mentioned in the drawing / instruction of engineer in charge. Cost includes formworks using rubber mould, Rate providing and laying paver blocks as per required grading and specification. The paver block shall be mechanically compacted. The work of paving blocks shall be executed in line and level by skill mason of flooring work only. It should be laid in such a way that the no cutting of the paver block to be necessary. if cutting of paver block necessary then it should be cut by machine only and carting. The finished surface of the paver block shall have resonably good, plain finished. Paver blocks shall be compacted and shall be relaid if necessary. Gravel or such type of materials shall not be allowed for production. Laying on 5 cms thick sand bedding	429.00	Smt	ARC Rate		

Sr.	Item Description	Rate	Per	Rate Reference		
				SOR	I.Code	P.no.
4	Labour work for fixing interlocking blocks / any kind of pavement on up to 50 mm th sand bedding, levelling, watering and fixing in line & level as well cleaning the site etc.comp. as directed.	78.00	Smt	ARC Rate	10	Foot path
5	Conveyance charge for C.C blocks / Nibhada , WT Curb of any design from any site of work to any AMC store within limit incl. loading, unloading etc comp as directed. ( without breakage )	3.00	No.	ARC Rate	5	Foot path
6	Labour work for fixing any kind of paving with cement pointing in CM 1:2, including watering, ramming etc comp. as directed			ARC Rate	7	Foot path
	For pavement					
a	Laying on Sand bedding as per requirement to fix the C.C.Block / Nibhada Stone in Line & Level.	78.00	Smt			
b	For Water Table & Kerb on Sand bedding as per requirement to fix the C.C.Block / Nibhada Stone in Line & Level.	35.00	Rmt			
7	P/L brickbats sand concrete (1:2) of one part of sand and two part of old brickbats including spreading, laying, ramming, watering and consolidation etc complete as directed.	350.00	Cmt	ARC Rate		
8	Supplying and fixing Nimbhada ladi 37 to 50 mm thick for walk-way, covering the activity of excavation, ramming, Laying on sand bedding as per requirement to fix the Nibhada Stone in Line & Level with cement pointing in cement mortar 1:2 etc complete as directed.	265.00	Smt	ARC Rate		