

AHMEDABAD MUNICIPAL CORPORATION						
SOR - (Jan. -2016) for Road Grouting Works Below 60 ft.						
Sr.	Item Description	Rate	Per	Rate Reference		
				SOR	I.Code	P.no./R.A
1	Box cutting the read surface in all sorts of soil, murrum to proper slope & camber for making a base for road work including removing the excavated stuff & depositing on the road side as directed upto 50.00 mt. Lead	64.74	Cmt.	R&B 2015-16	26008	14
2	Conveyance charge of earth, lime, murrum, building rubbish, manual garbage, sludge, excavated rock , fly ash, aggregate of any kind etc complete up to 5.0 KM lead.	133.18	Cmt	R&B 2015-16	3.2.1 A	80
3	Supplying of graded hand brocken stone size of 90 mm to 127 mm at site (Rubble or Spoul)	683.00	Cmt	ARC Rate	RA	841.50
4	Labour charges for spreading the spouls 127 mm thick layer good earth filling in voids correcting the grade & camber comp. with rolling, watering, incl. preparing the surface by brushing for removing all loose or dirts ect.comp.	18.00	Smt	ARC Rate	RA	24.95
5	Labour work for reinstatement of asphalt pavement upto soling level carryout with necessary excavation up to soiling level , watering, consolidation using selected excavated road materials like spouls, matels, bitumen popda etc including carting/recarting the material from the staking site, etc. comp. as directed.	50.00	Smt			
6	Supply of graded machine cut black trap stone aggregate (metal) of Sevaliya / Tima or equivalent quality metal of size 25 mm to 40 mm.	975.00	Cmt	ARC Rate	RA	924.00
7	Labour work for spreading the metal 85 mm thick in single layer, incl. providing & applying bitumen for semi grouting 2.5 kgs/sqm. & Providing & spreading the key black trap aggregate of good quality on top at the rate of 0.013 cmt. per sq.m. of size 18 mm passing in 9.5 mm retain rolling with 10 tonne roller etc. comp. as directed.	126.35	Smt	ARC Rate	RA	135.42
8	Supplying and Spreading good quality coarse sand free from Impurities including Transporation to Site and labour cost for Spreading etc. Comp. as directed.	350.00	cmt	(Building SOR 15-16, P-5, Iteam No.178 and P-33 Iteam no. 43)		
9	Repairing damaged M.H. and rasing M.H. up to road level incl. removing damaged brick work and repairing by brick masonry in C.M. 1:5 and plaster in C.M. 1:3 and fixing C.I. steps and existing MH sheet cover, removing the debris from MH and carting the same as directed. (Based on Drainage SOR 2009-10)					
	(A) up to 0.15 mt. (@ Two Coarse)	820.00	No.	ARC Rate		
	(B) up to 0.35mt. (@ Four Coarse)	1300.00	No.	ARC Rate		
	(C) up to 0.65 mt. (@ Seven Coarse)	2010.00	No.	ARC Rate		

Sr.	Item Description	Rate	Per	Rate Reference		
				SOR	I.Code	P.no./R.A
	(D) up to 0.90 mt. (@ Ten Coarse)	2420.00	No.	ARC Rate		
10	Repairing damaged I.C./ Raising removing damaged brick work and repairing by brick masonry in C.M. 1:5 and plaster in C.M. 1:3 and fixing C.I. steps and existing chamber sheet cover, removing the debris from chamber and carting the same as directed. (Based on Drainage SOR 2009-10)	450.00	Nos.	Based on Drainage SOR 2009-10		
11	Carting and Fixing M.H., Chamber or Catchpits Seat and Cover in line and level to match existing road level in C.C. 1:2:4 and finishing smooth, watering and protecting for 7 days etc. complete as directed. M.H. seat cover will be supplied by A.M.C.(from any store) (Based on Drainage SOR 2009-10)	840.00	No.	Based on Drainage SOR 2009-10		